



Addendum No. 5
Memorial Park Dog Park and Community Garden Parking Lot
CITY OF WILSONVILLE PROJECT #9132

ISSUE DATE: August 21, 2018

TO: PLAN HOLDERS (Quest CDN #5879785)

FROM: Kerry Rappold, Natural Resources Manager

RE: REVISIONS TO BIDDING DOCUMENTS

The following Addenda to the Bidding Documents shall be considered merged with the original bid package as if they were whole. Contractor shall acknowledge receipt of this Addendum in Section 24 of the Bid Proposal.

BID DATE & TIME: August 23, 2018 at 2:00 pm (REVISED)

CLARIFICATIONS

ITEM #1: The following question was submitted: "Is the contractor responsible for surveying"

The project-specific special provisions ((00150.15) state the contractor shall provide construction staking for the work. Construction staking will be incidental to the work and no separate payment will be made.

ITEM #2: A new bid schedule is provided that includes the new bid items (i.e., Item 68 – Removable Bollard; Item 69 – Wheel Stop).

ITEM #3: Due to the revised Bid Opening date (**August 23, 2018 at 2 pm**) the schedule has been updated with the following dates:

Evaluation of Proposals Complete	August 24, 2018
Notice of Intent to Award	August 24, 2018
Award Protest Deadline	August 31, 2018

(All other dates remain the same)

END OF ADDENDUM #5

City of Wilsonville

BID SCHEDULE

Community Garden Parking Area

ITEM #		QUANTITY	UNIT	UNIT PRICE	COST
1	Mobilization (Not to exceed 5% of total Bid)	1	L.S.		
2	Traffic Control	1	L.S.		
3	Tree Protection Fence	235	L.F.		
4	Construction Fencing	920	L.F.		
5	Clearing and Grubbing	1	L.S.		
6	Stripping/Haul-Off	575	C.Y.		
7	Earthwork	1	L.S.		
8	Haul-Off	1	L.S.		
9	Demolition	1	L.S.		
10	Ditch Inlet Protection	2	EA.		
11	Sediment Fence	955	L.F.		
12	Straw Waddles	45	L.F.		
13	Construction Entrance	1	L.S.		
14	Concrete Washout	1	EA.		
15	Level 2, 1/2" ACP Mixture - Base Lift	200	TN		
16	Level 2, 1/2" ACP Mixture - Top Lift	200	TN		
17	1.5"-0 Aggregate Base	2,000	S.Y.		
18	3/4"-0 Aggregate Base	1,800	S.Y.		
19	Standard Curb	380	L.F.		
20	Mountable Curb	425	L.F.		
21	Geotextile Fabric	2,170	S.Y.		
22	PCC: Traffic Rated Pavement	3,030	S.F.		
23	PCC: Sidewalk Pavement	4,330	S.F.		
24	Valley Gutter	200	L.F.		
25	Truncated Domes on New Surfaces	2	EA.		
26	48" Manhole	1	EA.		
27	8" PVC 3034	215	L.F.		
28	6" Perforated ABS SCH 40	30	L.F.		
29	12" Concrete Culvert	40	L.F.		
30	Growing Medium	1	L.S.		
31	River Rock	3	EA.		
32	Washed Drain Rock	120	C.Y.		
33	Open Graded Aggregate	20	C.Y.		
34	Beehive Overflow Inlet and Grate	1	EA.		
35	Sanitary Cleanout	2	EA.		
36	4" ABS Lateral	105	L.F.		
37	4" PVC Lateral	35	L.F.		
38	Connect to Existing Sanitary Manhole	1	EA.		
39	Fire Hydrant	1	EA.		
40	1" PEX Pipe	245	L.F.		
41	Tap Existing Water w/ 6"x6" Saddle	1	L.S.		
42	Tap Existing Water w/ 1" Saddle	2	EA.		
43	Abandon Existing Water Meter	1	EA.		
44	Light Pole	4	EA.		
45	Conduit	464	L.F.		
46	Timber Bridge Modification	1	L.S.		
47	Pedestrian Crossing Sign R1-6a	1	EA.		
48	Pedestrian Crossing Sign (W11-2 and W16-9P)	3	EA.		
49	Traffic Delineator (Type 2 Yellow)	5	EA.		
50	Speed Limit Sign (R2-1)	2	EA.		

City of Wilsonville

ITEM #		QUANTITY	UNIT	UNIT PRICE	COST
51	Gravel Shoulder (8" thick)	1,475	S.F.		
52	4" Wide Solid White Stripe	550	L.F.		
53	8" Wide Solid White Stripe	60	L.F.		
54	Yield Sign (R1-2)	2	EA.		
55	One Lane Bridge Sign (W5-3)	2	EA.		
56	Custom "Do Not Block Driveway" Sign (R10-7)	1	EA.		
57	Bicycle Parking Loops	3	EA.		
58	Restroom Building (Site Prep)	1	LS		
59	Singage	4	EA.		
60	Parking Stall Striping	30	EA.		
61	ADA Logo	2	EA.		
62	Diagonal Striping	320	S.F.		
63	2" Caliper Trees	10	EA.		
64	2 Gallon Shrubs	203	EA.		
65	4" Special Container	2,440	EA.		
66	Upland Seeding	16,740	S.F.		
67	Irrigation System	1	LS		
68	Removalble Bollard	2	EA		
69	Wheel Stop	32	EA		

Grand Total (In numbers):

Grand Total (In writing):
